

## Technische Daten Company Building 08, 09 und 10

	CB08	CB09	CB10
BGF in m <sup>2</sup> (exkl. TG)	8170	8331	9326
MF in m <sup>2</sup> (exkl. TG)	6440	6522	6650
MF/BGF	79%	78%	71%
Baukosten (exkl. MSW, inkl. TG)	8,4 Mio. EUR	10,3 Mio. EUR	10,2 Mio. EUR
GIK	14,4 Mio. EUR	16,7 Mio. EUR	16,7 Mio. EUR
Höhe (ca.)	+36,5 m WN	+34 m WN	+39,3 m WN
Abmessungen	43m x 19m	43m x 29m	42m x 29m
m <sup>3</sup> umbauter Raum	29.000	36.000	38.000
Betonmenge [m <sup>3</sup> ]	22000		
Stahlmenge [t]	2000		
Geschossanzahl inkl. UG	10	11	11
AP/m <sup>2</sup>	17-20 m <sup>2</sup> /AP	17-20 m <sup>2</sup> /AP	17-20 m <sup>2</sup> /AP

